

NAME OF WORK :- CONSTRUCTION OF BASKET BALL PLAY GROUND AT ABHAYAPURI COLLAGE

NAME OF COLLAGE :- ABHAYAPURI COLLAGE

DISTRICT :- ABHAYAPURI ,BONGAIGAON , ASSAM

SCHEDULE OF WORK / ITEMS FOR BASKETBALL PLAYGROUND

ITEM NO.	PARTICULARS OF ITEMS	QNTY	UNITS	RATE IN FIGURE (INR)	RATE IN WORD	AMOUNT
<u>Item No : 1 /</u> <u>1.1 APWD</u> <u>SOR 2013-14</u>	Earthwork in excavation for foundation trenches of walls, retaining walls, footings of column, steps, septic tank etc. including refilling (return filling) the quantity as necessary after completion of work, breaking clods in return filling, dressing, watering and ramming etc. and removal of surplus earth with all lead and lifts as directed and specified in the following classification of soils including bailing out water where necessary as directed and specified.	31.25	Cum			
<u>Item No : 2 /</u> <u>4.1.6 SRO</u> <u>APWD 2013-</u> <u>14 (building)</u>	230mm thick brick wall in cement mortar with 1st class brick including racking out joints and curing complete as directed in structure (i) In Sub-structure upto plinth level including dewatering if necessary (a) In proportion 1:3 (b) In proportion 1:4	100.41	sqm			
Item No.3 /1.3	Earth / sand filling in plinth in layers not then 150mm thick including necessary carriage watering ramming etc. complete as directed and specified including payment of land compensation forest royly tax and other duties and taxex as may be necessary (C) With sit (prdominantly non plastic) carriage including loading and unload	382.15	cum			
<u>Item No :4</u> <u>/4. 1.1 SRO</u> <u>APWD 2013-</u> <u>14 (building)</u>	Providing brick soling in foundation and under floor at all levels with stone/best quality picked jhama bricks, and sand packed and laid to level and in panel after labour and materials etc.complate as directed. (a)Brick on flat soling.....	383.43	sqm			

<p><u>Item No : 5</u> <u>/18.1.1 SRO</u> <u>APWD 2013-</u> <u>14 (building)</u></p>	<p>Supplying, fitting and fixing in position reinforcement bars conforming to relevant I.S. Code for R.C.C. work/ R.B. walling including straightening, cleaning, cutting and bending to proper shapes and length as per details, supplying and binding with 20G annealed black wire and placing in position with proper blocks, supports, chairs, spacers etc. complete (upto 1st floor level).</p>	<p>11.88</p>	<p>qtl</p>			
<p>Item No : 6 / 2.1.1 APWD SOR 2013-14</p>	<p>PCC(Plain cement concrete)works with coarse aggregate of sizes 13 mm to 32 mm in foundation bed for footing steps, walls, bricks etc. as directed and specified including dewatering if necessary shall be measured and paid separately. (a) In prop 1 cement : 3 sand : 6 Coarse aggregate by volume</p>	<p>63.83</p>	<p>cum</p>			
<p>Item No : 7 / 3.1.1.3 APWD SOR 2013-14</p>	<p>17.10 Supplying, fitting and fixing chain link fencing of Sqm 10 S.W.G, G.I. Wire 50mm x50mm mesh fitted to M.s angle iron post at 2000mm apart of specification detailed below including supplying, fitting and fixing hooks, eye bolts with nuts, staples and bolts including three horizontal lines of G.I wire 10 S.W.G at top,middle and bottom and with one vertical line to each fencing post for keeping the fencing tight and erect complete, including one coat of primer painting to M.S angle iron post in P.C.C base etc. with following.a) Corner and end posts with M.S angle of size 50mmx50mmx 5mm and length not less than 1800mm only duly slotted and bottom torqued with two numbers as stay posts. b) Intermediate post with M.S angle of size 40mmx40mmx5mm and length not less than 1800mm only duly slotted and bottom torqued and splayed. c) Stay post with M.s angle of size 35 mmx35mmx5mm and length not less than 1800mm duly slotted and bottom torqued and splayed. All M.S angle iron posts are to be fitted to P.C.C base embedded not less than 600mm (P.C.C. work shall be measured and paid separately)</p>	<p>441</p>	<p>sqm</p>			

Item No : 8 / 3.1.1.3 APWD SOR 2013-14	Providing from work of ordinary timber planking so as to give a rough finish including centering shuttering and propping etc, height of propping and centering below supporting floor to ceiling not exceeding 4.0 m and removal of the same for in situ reinforced concrete and plain concrete work in : columns , pillars , posts & strut a) using 25 mm thick plank	8	sqm			
Item No :8	providing Marking Lining by 2 coats of High Quality Floor Paint and line marking paint by cleaning scraping etc.	420	sqm			
Item No : 9	basket ball fiber board including all fitting and fixture items	1	set			
Item No : 10	basket ball HIGH QUALITY	4	Nos			
Item No : 11	Score Board HIGH QUALITY	1	Set			
TOTAL						

Signature of Bidder (with seal wherever applicable)